

Response Strategy Site: Mesmer Ave (BAL-033)								
Site Description and Field Notes								
Site Location/Segment: BAL-LA-B-033	Site Description and Field Notes: Limited staging on south side of the creek within the gated entrance. Sepulveda channel outfall located to the east upstream. Personnel access to the channel bottom from the gated entrance on Mesmer Ave. and the bike path by walking down the sloped bank.							
Gradient: Low	River Width: 20 meters (66 feet)	Vehicular Access: Passenger vehicles, small trucks, and small trailers.	Recreational Use: N/A	Boat Launches: N/A				
Site Contact/s:	LA County Puk (800) 675-4357 (562) 861-0316 (626) 458-4357	27/7		<u>.</u>				
ESI Shoreline Type:	1B Exposed, solid man-made structures; 8F Vegetated, steeply-sloping bluffs; 9B Vegetated low banks; 10B Freshwater marshes							

Site Images

Upstream



Downstream



Straight Across



RR = River Right RL = River Left

Entrance



Photo Date: 9/11/2023

Page 3 of 3

Response Strategy Site: Mesmer Ave (BAL-033)

Site Objectives: Sandbag dam and/or boom to prevent further movement of oil and allow for collection of oil.

Implementation: Construct sandbag underflow dam upstream of creek adjacent to the Sepulveda channel outfall with a minimum of 3 ft. high. Deploy boom to consist of 200 ft. of containment boom with a minimum of a 45-degree angle utilizing anchor points. Use a leader rope to deploy boom across the creek with boom attached.

Staging Area Location and Capabilities/Amenities/Waste Management: Limited on south side of the creek. Boom trucks, trailer, vacuum trucks and temporary storage tanks could use the space within the gated entrance on Mesmer Ave., but it is limited and narrow.

Response Strategy Map (overview)



Table of Response Resources							
Туре	Sub-Type	Size	Unit	Quantity	Special Equipment or Comments		
Sandbags					Sandbag dam minimum of 3 ft. high		
Piping					For sandbag dam underflow		
Boom	Swiftwater, Swamp, or Harbor	8, 12, or 18 in. skirt	Feet	200			
Rope			Feet	200	For leader on boom deployment		
Personnel			Crew	4			